Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
cross road-4	1	20.00	1.20	0.225	5.40			
Dist.4 main	1	123.00	1.20	0.225	33.21			
Dist.4 cross	1	133.00	1.20	0.225	35.91			
cross road-5	1	137.00	1.20	0.225	36.99			
cross road-6	1	148.00	1.20	0.225	39.96			
cross road-7	1	64.00	1.20	0.225	17.28			
Dist cross	1	33.00	1.20	0.225	8.91			
2nd main	1	110.00	1.20	0.225	29.70			
2nd main- Mery school	1	205.00	1.20	0.225	55.35			
cross road-10	1	37.00	1.20	0.225	9.99			
2nd main	1	165.00	1.20	0.225	44.55			
cross road	1	350.00	1.20	0.225	94.50			
Bad reaches	12	14.00	6.50	0.225	245.70			
					738.45	**Cum**	**1962.57**	**1449258.93**
Providing and applying primer coat with ss bitumen emulsion on prepared surface of granular base such as WMM including clearing of road surface and spraying primer at the rate of 0.60 kg/sqm using mechanical means complete as per specifications. MORTH Specification No.502 (PWD No.160/It No.21.6)								
Basic rate	26.00							
12.5% AD-HOC	2.86							
Sub Total-1	28.86							
6% AIW	1.73							
Sub Total-2	30.59							
SBS-407								
cross road-1	1	100.00	1.20		120.00			
cross road-2	1	30.00	1.20		36.00			
cross road-3	1	170.00	1.20		204.00			
cross road-4	1	20.00	1.20		24.00			
Dist.4 main	1	123.00	1.20		147.60			
Dist.4 cross	1	133.00	1.20		159.60			
cross road-5	1	137.00	1.20		164.40			
cross road-6	1	148.00	1.20		177.60			
cross road-7	1	64.00	1.20		76.80			
Dist cross	1	33.00	1.20		39.60			
2nd main	1	110.00	1.20		132.00			
2nd main- Mery school	1	205.00	1.20		246.00			
cross road-10	1	37.00	1.20		44.40			
2nd main	1	165.00	1.20		198.00			
cross road	1	350.00	1.20		420.00			
Bad reaches	12	14.00	6.50		1092.00			
SBS-407 - Profile correction								
cross road-1	1	100.00	2.00		200.00			
cross road-2	1	30.00	3.00		90.00			
cross road-3	1	170.00	2.50		425.00			
cross road-4	1	20.00	2.80		56.00			
Dist.4 main	1	123.00	2.00		246.00			
Dist.4 cross	1	133.00	2.40		319.20			
cross road-5	1	137.00	2.70		369.90			
cross road-6	1	148.00	3.00		444.00			

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	cross road-7	1	64.00	2.00		128.00			
	1st cross	1	33.00	2.10		69.30			
	2nd main	1	110.00	1.90		209.00			
	2nd main- Mery school	1	205.00	3.10		635.50			
	cross road-10	1	37.00	3.50		129.50			
	3rd main	1	165.00	2.60		429.00			
	cross road	1	350.00	2.40		840.00			
						7872.40	**Sqm**	**30.59**	**240829.31**
	KSRRB M500- 15. Providing, laying dense graded bituminous macadam using 40/60 TPH capacity H.M.P with Mechanical paver Gr-II (50mm to 75mm), crushed aggregates of specified grading premixed with 4.5% VG 30 grade bituminous binder and , transporting the hot mix to work site , laying to the required level and grade, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MORTH table 500-10 complete in all respects complete as per specifications MORTH Specification No.507 (P.No.162&163 Pc.No.21.17.6)								
	Basic rate	6717.00							
	10% AD-HOC	738.87							
	Sub Total-1	7455.87							
	6% AW	447.35							
	Sub Total-2	7903.22							
	SPS 407								
	cross road-1	1	100.00	1.20	0.05	6.00			
	cross road-2	1	30.00	1.20	0.05	1.80			
	cross road-3	1	170.00	1.20	0.05	10.20			
	cross road-4	1	20.00	1.20	0.05	1.20			
	3rd 4 main	1	123.00	1.20	0.05	7.38			
	3rd 4 cross	1	133.00	1.20	0.05	7.98			
	cross road-5	1	137.00	1.20	0.05	8.22			
	cross road-6	1	148.00	1.20	0.05	8.88			
	cross road-7	1	64.00	1.20	0.05	3.84			
	1st cross	1	33.00	1.20	0.05	1.98			
	2nd main	1	110.00	1.20	0.05	6.60			
	2nd main- Mery school	1	205.00	1.20	0.05	12.30			
	cross road-10	1	37.00	1.20	0.05	2.22			
	3rd main	1	165.00	1.20	0.05	9.90			
	cross road	1	350.00	1.20	0.05	21.00			
	Bad reaches	12	14.00	6.50	0.05	54.60			
	SPS 407 - Profile correction								
	cross road-1	1	100.00	2.00	0.05	10.00			
	cross road-2	1	30.00	3.00	0.05	4.50			
	cross road-3	1	170.00	2.50	0.05	21.25			
	cross road-4	1	20.00	2.80	0.05	2.80			
	3rd 4 main	1	123.00	2.00	0.05	12.30			
	3rd 4 cross	1	133.00	2.40	0.05	15.96			
	cross road-5	1	137.00	2.70	0.05	18.50			
	cross road-6	1	148.00	3.00	0.05	22.20			
	cross road-7	1	64.00	2.00	0.05	6.40			
	1st cross	1	33.00	2.10	0.05	3.47			
	2nd main	1	110.00	1.90	0.05	10.45			

Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
2nd main- Mery school	1	205.00	3.10	0.05	31.78			
cross road-10	1	37.00	3.50	0.05	6.48			
2nd main	1	165.00	2.60	0.05	21.45			
cross road	1	350.00	2.40	0.05	42.00			
					393.62	**Cum**	**7903.22**	**3110866.32**
KSRRB 500-7:Providing and applying tack coat with bitumen emulsion using 80/100 grade bitumen (VG20) on the prepared black toped suface at 2.5kg per 10 sqm, heating bitumen in boiler fitted with spray set (Excluding cleaning of road surface) including cost of all materials, labour, HOM of Machineries complete as per Specifications.(P.No.160 & I.No.21.7)								
Basic rate	11.00							
10% AD-HOC	1.21							
Sub Total-1	12.21							
6% AW	0.73							
Sub Total-2	12.94							
SPS 407								
cross road-1	1	100.00	6.80		680.00			
cross road-2	1	30.00	8.50		255.00			
cross road-3	1	170.00	5.80		986.00			
cross road-4	1	20.00	6.80		136.00			
1st A main	1	123.00	5.00		615.00			
1st A cross	1	133.00	5.70		758.10			
cross road-5	1	137.00	5.90		808.30			
cross road-6	1	148.00	6.00		888.00			
cross road-7	1	64.00	5.00		320.00			
1st A main	1	273.00	4.30		1173.90			
1st B main	1	235.00	4.90		1151.50			
1st cross	1	33.00	5.00		165.00			
2nd main	1	110.00	4.00		440.00			
2nd main- Mery school	1	205.00	6.50		1332.50			
cross road-8	1	33.00	4.00		132.00			
cross road-9	1	38.00	3.50		133.00			
2nd B main	1	182.00	4.60		837.20			
cross road-10	1	37.00	7.50		277.50			
1st main	1	165.00	5.20		858.00			
cross road	1	350.00	5.50		1925.00			
					13872.00	**Sqm**	**12.94**	**179539.75**
KSRRB M500- 15. Providing, laying bituminousConcrete using 40/60 THP capacity H.M.P with Mechanical paver Gr-II (30mm to 45mm), crushed aggregates of specified grading premixed with 5.4% VG 30 grade bituminous binder and , transporting the hot mix to work site , laying to the required level and grade,rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MORTH Specification clause No.500.9 complete in all respects complete as per specifications MORTH Specification No.509 (P.No.164 Item No.ZII.22.6)								
Basic rate	7659.00							
10% AD-HOC	842.49							
Sub Total-1	8501.49							
6% AW	510.09							
Sub Total-2	9011.58							
SPS 407								
cross road-1	1	100.00	6.80	0.04	27.20			

Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
Cross road-2	1	30.00	8.50	0.04	10.20			
Cross road-3	1	170.00	5.80	0.04	39.44			
Cross road-4	1	20.00	6.80	0.04	5.44			
Dist.A main	1	123.00	5.00	0.04	24.60			
Dist.A cross	1	133.00	5.70	0.04	30.32			
Cross road-5	1	137.00	5.90	0.04	32.33			
Cross road-6	1	148.00	6.00	0.04	35.52			
Cross road-7	1	64.00	5.00	0.04	12.80			
Dist.A main	1	273.00	4.30	0.04	46.96			
Dist.B main	1	235.00	4.90	0.04	46.06			
Dist cross	1	33.00	5.00	0.04	6.60			
Dist main	1	110.00	4.00	0.04	17.60			
Dist main- Mery school	1	205.00	6.50	0.04	53.30			
Cross road-8	1	33.00	4.00	0.04	5.28			
Cross road-9	1	38.00	3.50	0.04	5.32			
Dist B main	1	182.00	4.60	0.04	33.49			
Cross road-10	1	37.00	7.50	0.04	11.10			
Dist main	1	165.00	5.20	0.04	34.32			
Cross road	1	350.00	5.50	0.04	77.00			
					554.88	**Cum**	**9011.58**	**5000345.18**
MORTH M800-13: Road marking with hot applied thermoplastic compound with reflect rising glass beads on bituminous surface- providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads at 250 gms per sqm area, thickness of 2.5 mm inclusive of surface to level, uniform and free from streaks and holes complete as per specifications. MORTH specification No. 803, No. 1974 (P.No.185 & I.No.24.15)								
Basic rate	512.00							
15% AD-HOC	56.32							
Sub Total-1	568.32							
6% AIW	34.10							
Sub Total-2	602.42							
SBS-407								
Cross road-1	2	100.00	0.10		20.00			
Cross road-2	2	30.00	0.10		6.00			
Cross road-3	2	170.00	0.10		34.00			
Cross road-4	2	20.00	0.10		4.00			
Dist.A main	2	123.00	0.10		24.60			
Dist.A cross	2	133.00	0.10		26.60			
Cross road-5	2	137.00	0.10		27.40			
Cross road-6	2	148.00	0.10		29.60			
Cross road-7	2	64.00	0.10		12.80			
Dist.A main	2	273.00	0.10		54.60			
Dist.B main	2	235.00	0.10		47.00			
Dist cross	2	33.00	0.10		6.60			
Dist main	2	110.00	0.10		22.00			
Dist main- Mery school	2	205.00	0.10		41.00			
Cross road-8	2	33.00	0.10		6.60			
Cross road-9	2	38.00	0.10		7.60			
Dist B main	2	182.00	0.10		36.40			
Cross road-10	2	37.00	0.10		7.40			
Dist main	2	165.00	0.10		33.00			

Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
cross road	2	350.00	0.10		70.00			
					517.20	Sqm	602.42	311571.21
Providing and fixing pre cast solid **cement concrete kerb stones** made out of CC 1:2:4 with top and bottom width 114 and 165 mm respectively, 400mm high and 450mm in length finished with CM 1:3 plastering and finishing cutting including formwork, curing, including cost of materials, labour charges of machinery, loading and unloading, lead and lift, transportation etc.,complete (P.No-25, I No-5.30)								
Basic rate	313.00							
10% AD-HOC	34.43							
Sub Total-1	347.43							
6% AW	20.85							
Sub Total-2	368.28							
missing/damaged	2	220.00			440.00			
B = A/0.45				A	440.00			
				B	978.00	Nos	368.28	360173.73
KSRB 800-1. **Painting two coats** after filling the surface with synthetic enamel paint in approved shades on new plastered concrete surfaces, with materials, labour complete as per specifications. MORTH Chapter 8 (P.No-183, I No-24.1)								
Basic rate	60.00							
10% AD-HOC	6.60							
Sub Total-1	66.60							
6% AW	4.00							
Sub Total-2	70.60							
	2	2200.00	0.35		1540.00			
					1540.00	Sqm	70.60	108717.84
							Total Construction Cost	14780511.78
							DPR & PMC Charges	219400.00
							Sub Total	14999911.78
							Utility Shifting, Miscellaneous, Rounding off	88.22
							GRAND TOTAL	15000000.00

Certificate

1. The workspot was inspected and works is found to be necessary.
2. The area comes within the Bruhat Bangalore Mahanagara Palike limits.
3. The rates adopted based on the PWD SR,Bangalore circle for year 2016-2017, issue rates and Data Rates. 11% AD-HOC is added as per order issued on 06-02-2018

Assistant Engineer

Asst. Executive Engineer,

Executive Engineer,
Yelahanka Division,
BBMP Bangalore
7/2/18

Administrative Approval

Accorded For Rs. 150.00 Lakhs
Head of A/C P-2178
CER NO :193/17-18 Dt:23/3/2018

E.E. (Project)

Technical Sanction
Accorded For 150 Lacs
Head of A/C P-2178
CER NO : ..... Dt: Data base

TA

CE (YNK)

Bruhat Bangalore Mahanagara Palike
Excecutive Engineer Yelahanka Division

Name of Work: Improvement of drains and resurfacing to roads in SFS 707 area in ward no.03, Attur

					Estimate Cost Rs.			150.00 Lakhs
Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
Removing & Refixing Stone Slabs of drains and Pointing in C.M(1:3). (Page No 25., I.No.5.33 of KPWD S.R 2016-17)								
Basic rate	76.00							
11% AD-HOC	8.36							
Sub Total-1	84.36							
6% AW	5.06							
Sub Total-2	89.42							
SFS 707								
Top slab								
SFS 707								
3rd cross	2	410.00	1.00		820.00			
cross road-1	2	79.00	1.00		158.00			
cross road-2	2	33.00	1.00		66.00			
Bus stand	2	256.00	1.00		512.00			
cross road-3	2	134.00	1.00		268.00			
cross road-4	2	285.00	1.00		570.00			
cross road-5	2	88.00	1.00		176.00			
Opp Govt cenral lib	2	84.00	1.00		168.00			
Ganapathi temple	2	101.00	1.00		202.00			
cross road-7	2	98.00	1.00		196.00			
Drain slab								
SFS 707								
3rd cross	2	410.00	1.65		1353.00			
cross road-1	2	79.00	1.65		260.70			
cross road-2	2	33.00	1.65		108.90			
Bus stand	2	256.00	1.65		844.80			
cross road-3	2	134.00	1.65		442.20			
cross road-4	2	285.00	1.65		940.50			
cross road-5	2	88.00	1.65		290.40			
Opp Govt cenral lib	2	84.00	1.65		277.20			
Ganapathi temple	2	101.00	1.65		333.30			
cross road-7	2	98.00	1.65		323.40			
Total Qty					**8310.40**			
Consider 30% of total Qty					**2493.12**			
					2493.12	**Sqm**	**89.42**	**222938.78**
Providing granite slabs of selected quality roughly dressed and fixed in cement mortar (1:6) including fixing curing etc., complete. 7.5cm thick (Page No 25., I.No.5.31.1 of KPWD S.R 2016-								
Basic rate	628.00							
11% AD-HOC	69.08							
Sub Total-1	697.08							
6% AW	41.82							
Sub Total-2	738.90							
Consider 10% of Total qty of item no -1					831.04			
					831.04	**Sqm**	**738.90**	614059.44

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
3	Providing precast slab of 100 mm thick including cost of all materials, labour, curing,transportation,loading ,unloading,etc.,complete as per the direction of engineer in charge								
	Basic rate	2100.00							
	Consider 10% of Total qty of item no -1					313.60			
						313.60	**Sqm**	**2100.00**	**658560.00**
4	KSRRB 300-1. Earthwork excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 1.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications. MORTH / Chapter 3 (Page No142., I.No.19.1 of KPWD S.R 2016-17).								
	Basic rate	82.00							
	11% AD-HOC	9.02							
	Sub Total-1	91.02							
	6% AW	5.46							
	Sub Total-2	96.48							
	10km ld & lt, transport	100.00							
	Sub Total-3	196.48							
	SPS 707								
	3rd cross	2	410.00	0.50	0.50	205.00			
	cross road-1	2	79.00	0.50	0.50	39.50			
	cross road-2	2	33.00	0.50	0.50	16.50			
	Bus stand	2	256.00	0.50	0.50	128.00			
	cross road-3	2	134.00	0.50	0.50	67.00			
	cross road-4	2	285.00	0.50	0.50	142.50			
	cross road-5	2	88.00	0.50	0.50	44.00			
	Opp Govt cenral lib	2	84.00	0.50	0.50	42.00			
	Ganapathi temple	2	101.00	0.50	0.50	50.50			
	cross road-7	2	98.00	0.50	0.50	49.00			
	SPS 707								
	3rd cross	1	410.00	1.20	0.40	196.80			
	cross road-1	1	79.00	1.20	0.40	37.92			
	cross road-2	1	33.00	1.20	0.40	15.84			
	Bus stand	1	256.00	1.20	0.40	122.88			
	cross road-3	1	134.00	1.20	0.40	64.32			
	cross road-4	1	285.00	1.20	0.40	136.80			
	cross road-5	1	88.00	1.20	0.40	42.24			
	Opp Govt cenral lib	1	84.00	1.20	0.40	40.32			
	Ganapathi temple	1	101.00	1.20	0.35	42.42			
	cross road-7	1	98.00	1.20	0.35	41.16			
	Bed reaches	10	12.00	7.00	0.35	294.00			
	culvert	2	7.00	1.50	1.20	25.20			
						1843.90	**Cum**	**196.48**	**362291.68**
	KSRB 4-1.2: Providing and laying in position plain cement concrete of mix 1:3:6 with OPC cement @ 220kgs, with 40mm and down size graded granite metal coarse aggregates @ 0.890cum and fine aggregates @ 0.465cum machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications.Specification No.KBS 4.2 (P.12/I.4.2)/ PWD SR 2016-17								
	Basic rate	5046.00							
	11% AD-HOC	555.06							
	Sub Total-1	5601.06							

Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
6% AW	336.06							
Sub Total-2	5937.12							
CC Road								
CC Road -1	1	80.00	3.80	0.15	45.60			
CC Road -2	1	30.00	5.10	0.15	22.95			
CC Road -3	1	20.00	5.40	0.15	16.20			
CC Road -4	1	62.00	3.80	0.15	35.34			
CC Road -5	1	82.00	5.10	0.15	62.73			
CC Road -6	1	43.00	4.00	0.15	25.80			
CC Road -7	1	42.00	3.90	0.15	24.57			
CC Road -8	1	63.00	4.40	0.15	41.58			
CC Road -9	1	34.00	5.00	0.15	25.50			
culvert	2	7.00	1.50	0.15	3.15			
					303.42	**Cum**	**5937.12**	**1801442.04**
KSRB 5.3-3 : Providing and constructing granite / trap / basalt size stone masonry in basement with cement mortar 1:6, edges of stones chistle dressed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications. KBS 5.1.13 (P.23/I.5.9)/ PWD SR 2016-17								
Basic rate	5005.00							
10% AD-HOC	550.55							
Sub Total-1	5555.55							
6% AW	333.33							
Sub Total-2	5888.88							
culvert	4	7.00	0.45	0.70	8.82			
					8.82	**Cum**	**5888.88**	**51,939.95**
KSRB - 4-1.6: Providing and laying in position plain cement concrete of mix 1:2:4 with cement @ 240kgs, with 20mm and down size graded granite metal coarse aggregates at 0.78cum and fine aggregates at 0.459 cum, machine mixed, concrete laid in layers not exceeding 15 cms.thick, well compacted, in foundation, plinth and cills including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1,4.2. (P.No.12, No.4.6 of PW, P&IWTD SR 2016-17)								
Basic rate	5249.00							
10% AD-HOC	577.39							
Sub Total-1	5826.39							
6% AW	349.58							
Sub Total-2	6175.97							
culvert	4	7.00	0.45	0.10	1.26			
					1.26	**Cum**	**6175.97**	**7,781.73**
Providing precast slab of 250 mm thick including cost of all materials, labour, curing,transportation,loading ,unloading,etc.,complete as per the direction of engineer in charge (Data rate)								
Basic rate	5111.00							
	2	7.00	1.50		21.00			
					21.00	**Sqm**	**5111.00**	**107331.00**
KSRB M400-6.1. Construction of granular sub-base by providing close graded material, crushed stone aggregates of granite/trap/basalt material, mixing in a mechaical mix plant at OMC, carriage of mixed material to work site, spreading in uniform layers with motor grader on prepared surface and compacting with vibratory power roller to achieve the desired density, complete as per specifications. A. Plant Mix Method.Close graded granular sub-base material as per 400-1 For Grading- II Material (Page No 155., I.No.20.4.2 of KPWD S.R 2016-17).								
Basic rate	1571.00							
10% AD-HOC	172.81							

Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
Sub Total-1	1743.81							
6% AW	104.63							
Sub Total-2	1848.44							
SPS 707								
3rd cross	1	410.00	1.20	0.150	73.80			
cross road-1	1	79.00	1.20	0.150	14.22			
cross road-2	1	33.00	1.20	0.150	5.94			
Bus stand	1	256.00	1.20	0.150	46.08			
cross road-3	1	134.00	1.20	0.150	24.12			
cross road-4	1	285.00	1.20	0.150	51.30			
cross road-5	1	88.00	1.20	0.150	15.84			
Opp Govt cenral lib	1	84.00	1.20	0.150	15.12			
Ganapathi temple	1	101.00	1.20	0.150	18.18			
cross road-7	1	98.00	1.20	0.150	17.64			
Bad reaches	10	12.00	7.00	0.150	126.00			
					408.24	Cum	1848.44	754606.57
KSRRB M400- Wet Mix Macadam - KSRRB M400-17. Providing, laying, spreading and compacting graded stones aggregate to wet mix macadam specifications including pre mixing the material with water at OMC in mechanical mix plant carriage of mixed method of tipper to site, laying in uniform layers with paver in sub-base/base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specifications. MORTH Specification No. 406 (P.No.158 I.No.20.18)								
Basic rate	1668.00							
10% AD-HOC	183.48							
Sub Total-1	1851.48							
6% AW	111.09							
Sub Total-2	1962.57							
SPS 707								
3rd cross	1	410.00	1.20	0.225	110.70			
cross road-1	1	79.00	1.20	0.225	21.33			
cross road-2	1	33.00	1.20	0.225	8.91			
Bus stand	1	256.00	1.20	0.225	69.12			
cross road-3	1	134.00	1.20	0.225	36.18			
cross road-4	1	285.00	1.20	0.225	76.95			
cross road-5	1	88.00	1.20	0.225	23.76			
Opp Govt cenral lib	1	84.00	1.20	0.225	22.68			
Ganapathi temple	1	101.00	1.20	0.225	27.27			
cross road-7	1	98.00	1.20	0.225	26.46			
Bad reaches	10	12.00	7.00	0.225	189.00			
					612.36	Cum	1962.57	1201798.63
Providing and applying primer coat with ss bitumen emulsion on prepared surface of granular base such as WMM including clearing of road surface and spraying primer at the rate of 0.60 kg/sqm using mechanical means complete as per specifications. MORTH Specification No.502 (P.No.160/lt No.21.6)								
Basic rate	26.00							
10% AD-HOC	2.86							
Sub Total-1	28.86							
6% AW	1.73							
Sub Total-2	30.59							
SPS 707								
3rd cross	1	410.00	1.20		492.00			
cross road-1	1	79.00	1.20		94.80			

Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
cross road-2	1	33.00	1.20		39.60			
Bus stand	1	256.00	1.20		307.20			
cross road-3	1	134.00	1.20		160.80			
cross road-4	1	285.00	1.20		342.00			
cross road-5	1	88.00	1.20		105.60			
Opp Govt cenral lib	1	84.00	1.20		100.80			
Ganapathi temple	1	101.00	1.20		121.20			
cross road-7	1	98.00	1.20		117.60			
Bad reaches	10	12.00	7.00		840.00			
SFS 707 - Profile correction								
SFS 707								
2nd cross	1	410.00	2.30		943.00			
cross road-1	1	79.00	2.10		165.90			
cross road-2	1	33.00	2.60		85.80			
Bus stand	1	256.00	2.50		640.00			
cross road-3	1	134.00	2.00		268.00			
cross road-4	1	285.00	2.30		655.50			
cross road-5	1	88.00	2.40		211.20			
Opp Govt cenral lib	1	84.00	2.00		168.00			
Ganapathi temple	1	101.00	2.00		202.00			
cross road-7	1	98.00	2.50		245.00			
					6306.00	Sqm	30.59	192910.63
MORRB M500- 15. Providing, laying dense graded bituminous macadam using 40/60 TPH capacity H.M.P with Mechanical paver Gr-II (50mm to 75mm), crushed aggregates of specified grading premixed with 4.5% VG 30 grade bituminous binder and , transporting the hot mix to work site , laying to the required level and grade, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MORTH table 500-10 complete in all respects complete as per specifications MORTH Specification No.507 (P.No.162&163 Cl.No.21.17.6)								
Basic rate	6717.00							
10% AD-HOC	738.87							
Sub Total-1	7455.87							
6% AW	447.35							
Sub Total-2	7903.22							
SFS 707								
2nd cross	1	410.00	1.20	0.05	24.60			
cross road-1	1	79.00	1.20	0.05	4.74			
cross road-2	1	33.00	1.20	0.05	1.98			
Bus stand	1	256.00	1.20	0.05	15.36			
cross road-3	1	134.00	1.20	0.05	8.04			
cross road-4	1	285.00	1.20	0.05	17.10			
cross road-5	1	88.00	1.20	0.05	5.28			
Opp Govt cenral lib	1	84.00	1.20	0.05	5.04			
Ganapathi temple	1	101.00	1.20	0.05	6.06			
cross road-7	1	98.00	1.20	0.05	5.88			
Bad reaches	10	12.00	7.00	0.05	42.00			
SFS 707 - Profile correction								
SFS 707								
2nd cross	1	410.00	2.30	0.05	47.15			
cross road-1	1	79.00	2.10	0.05	8.30			

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	cross road-2	1	33.00	2.60	0.05	4.29			
	Bus stand	1	256.00	2.50	0.05	32.00			
	cross road-3	1	134.00	2.00	0.05	13.40			
	cross road-4	1	285.00	2.30	0.05	32.78			
	cross road-5	1	88.00	2.40	0.05	10.56			
	Opp Govt cenral lib	1	84.00	2.00	0.05	8.40			
	Ganapathi temple	1	101.00	2.00	0.05	10.10			
	cross road-7	1	98.00	2.50	0.05	12.25			
						315.30	**Cum**	**7903.22**	**2491885.96**
	KSRRB 500-7:Providing and applying tack coat with bitumen emulsion using 80/100 grade bitumen (VG20) on the prepared black toped suface at 2.5kg per 10 sqm, heating bitumen in boiler fitted with spray set (Excluding cleaning of road surface) including cost of all materials, labour, HOM of Machineries complete as per Specifications.(P.No.160 & I.No.21.7)								
	Basic rate	11.00							
	11% AD-HOC	1.21							
	Sub Total-1	12.21							
	6% AW	0.73							
	Sub Total-2	12.94							
	SFS 707								
	3rd cross	1	410.00	6.20		2542.00			
	cross road-1	1	79.00	4.40		347.60			
	cross road-2	1	33.00	5.00		165.00			
	Bus stand	1	256.00	6.00		1536.00			
	cross road-3	1	134.00	4.10		549.40			
	cross road-4	1	285.00	5.60		1596.00			
	cross road-5	1	88.00	3.90		343.20			
	Opp Govt cenral lib	1	84.00	3.30		277.20			
	Ganapathi temple	1	101.00	3.40		343.40			
	cross road-7	1	98.00	3.80		372.40			
						8072.20	**Sqm**	**12.94**	**104475.26**
	KSRRB M500- 15. Providing, laying bituminousConcrete using 40/60 THP capacity H.M.P with Mechanical paver Gr-II (30mm to 45mm), crushed aggregates of specified grading premixed with 5.4% VG 30 grade bituminous binder and , transporting the hot mix to work site , laying to the required level and grade,rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MORTH Specification clause No.500.9 complete in all respects complete as per specifications MORTH Specification No.509 (P.No.164 Item No.21.22.6)								
	Basic rate	7659.00							
	11% AD-HOC	842.49							
	Sub Total-1	8501.49							
	6% AW	510.09							
	Sub Total-2	9011.58							
	SFS 707								
	3rd cross	1	410.00	6.20	0.04	101.68			
	cross road-1	1	79.00	4.40	0.04	13.90			
	cross road-2	1	33.00	5.00	0.04	6.60			
	Bus stand	1	256.00	6.00	0.04	61.44			
	cross road-3	1	134.00	4.10	0.04	21.98			
	cross road-4	1	285.00	5.60	0.04	63.84			
	cross road-5	1	88.00	3.90	0.04	13.73			
	Opp Govt cenral lib	1	84.00	3.30	0.04	11.09			
	Ganapathi temple	1	101.00	3.40	0.04	13.74			